

Management Plan (Sewerage)

1. Set goals
 - a) Manage, operate and maintain all parts of system.
 - b) Adequate capacity to convey peak flows.
 - c) Minimise frequency of overflows.
 - d) Mitigate impact of overflows.
2. Organisation
 - a) Identify responsible staff.
 - b) Set chain of communication.
3. Overflow emergency response plan
 - a) Notification of overflow.
 - b) Response.
 - c) Reporting.
 - d) Mitigate Impact.
4. Fat, Oil and Grease control Program
5. Legal authority
 - a) Control infiltration / inflow.
 - b) Design and construction of assets.
 - c) Installation, testing and inspection of assets.
6. Measures and activities.
 - a) Map of collection system.
 - b) Resources and Budget.
 - c) Prioritised preventive measures.
 - d) Scheduled inspection and condition assessment.
 - e) Contingency equipment and replacement Inspection.
 - f) Training.
7. Design and construction standards.
 - a) Installation, rehabilitation and repair.
 - b) Inspection and testing.
8. Capacity management.
 - a) Capacity assessment.
 - b) System evaluation and capacity assurance plan.
9. Monitoring, measurement and program modification
10. Audits